



cwdeckbuilders.com · (715) 544-7941 · info@cwdeckbuilders.com
906 N 16th Ave, Wausau, WI 54401 · Entity ID C138564 · EIN 41-5355234

PROJECT ESTIMATE · #2026-05-15-001 · Issued May 15, 2026 · Valid 14 days

PREPARED FOR

Debbie Overbeck

9409 Lambert St., Rothschild, WI 54474

(715) 393-7145

doverbeck1@gmail.com

ESTIMATOR

James Slogar, Owner

Central Wisconsin Deck Builders, LLC

(715) 544-7941

info@cwdeckbuilders.com

Project Overview

Single-coat paint-and-sealer refinish on an existing single-level pressure-treated wood deck. The job covers approximately **416 sq ft of deck floor**, **64 linear feet of railing system** (top rail, bottom rail, balusters, and posts), and **a 6-step staircase** (treads and risers). The deck is currently in fair condition. Work includes full surface preparation (power wash, sand rough spots, set nails, mask), application of a single coat of premium paint-and-sealer combination product in **slate gray**, and complete job-site protection and cleanup. The combined paint-and-sealer system delivers color, waterproofing, and UV protection in one product.

Scope of Work

- Move and protect homeowner furniture, grill, and personal items
- Cover and protect plants, landscaping, and adjacent siding
- Power-wash the entire deck surface, stairs, and railing system
- Light sanding of rough spots on floor boards, stair treads, and railing surfaces
- Set any raised or popped fasteners flush with the deck surface
- Apply one coat of premium paint-and-sealer combination product in slate gray
- Coat all visible wood surfaces: deck floor, all 6 stair treads, all 6 stair risers, top rails, bottom rails, balusters, and posts
- Final touch-ups, complete cleanup, and haul-off of all debris

Scope boundary: Work covers all visible wood surfaces above the deck floor and on the staircase. Underside of deck framing, joists, support posts below the deck floor, and any structural members hidden from normal view are not included. This is a single-coat application; heavily weathered boards may show some grain shadow through the finish. A second coat for full uniform coverage is available as an add-on after Coat 1 is reviewed.

Itemized Pricing

Item	Price
Surface preparation: power wash, sand rough spots, set fasteners, mask landscaping and siding	\$700
Premium materials (paint-and-sealer combination product, brushes, rollers, supplies)	\$750
Application of one coat to floor, 6 stairs, and full railing system in slate gray	\$1,100
Job site protection and cleanup	\$250
TOTAL FIXED PRICE	\$2,800

What's Included

- All materials: premium paint-and-sealer product, sandpaper, brushes, pads, rollers, drop cloths, masking
- All labor: approximately two working days (Day 1: preparation; Day 2: application)
- Full job-site protection of furniture, plants, and siding
- Post-job cleanup and debris haul-off
- **1-year limited warranty** against premature finish failure caused by defects in workmanship (excludes acts of nature, normal wear, and pre-existing structural conditions)

What's Not Included

- Second coat of paint-and-sealer for full uniform coverage (available as an add-on at \$1,100 after Coat 1 review)
- Repair or replacement of damaged or rotted boards (will be quoted separately if discovered during preparation)
- Hardware replacement (screws, nails, joist hangers, fasteners) beyond setting existing raised fasteners
- Structural repairs of any kind
- Removal of carpet, outdoor mats, planters, or built-in features
- Refinishing of pergolas, gazebos, or attached fences unless explicitly added to scope in writing
- Site power supply (homeowner provides access to a working exterior 120V outlet)

Schedule

Estimated start: Early June 2026 (week of June 1), weather permitting

Estimated duration: 2 working days (Day 1: surface preparation and masking; Day 2: single-coat application and cleanup).

Weather contingency: Application will be rescheduled if rain forecast exceeds 40% during the cure window. A minimum ambient temperature of 50°F day and night is required for proper finish cure.

Payment Terms

Stage	Amount
Deposit due on signed acceptance (30%)	\$840
Balance due on completion and walkthrough (70%)	\$1,960
Total	\$2,800

Accepted forms of payment: cash, check, credit or debit card, or digital payment (details provided upon acceptance)

Acceptance

This estimate becomes a binding work order upon homeowner signature and receipt of the 30% deposit. Estimate is valid for **14 days** from the date issued (May 15, 2026).

Homeowner signature

Date

Printed name:

Central Wisconsin Deck Builders, LLC

Date

By: James Slogar, Owner

Notice to Owner: Wisconsin Construction Lien Notice

As required by Wisconsin construction lien law (Wis. Stat. §779.02), the builder hereby notifies the owner that persons or companies furnishing labor or materials for construction work on the owner's land may have lien rights on the owner's land and buildings if they are not paid. The builder agrees to provide a list of all such persons supplying labor or materials upon request.